

AHMEDABAD MUNICIPAL CORPORATION

SOR - (Jan. -2016) fo Hot Mix Hand Laying patch work.

Sr.	Item Description	Rate	Per	Rate Reference		
				SOR	I.Code	P.no.
1	Labour charges for hand laying hotmix material DBM/BC on the road surface in line & level incl. cleaning the surface with wire brush and carting material by lari at place of work & rolling with 10 MT roller and sand spreading on seal coat after rolling etc. complete.	350.00	MT	ARC Rate		
2	Labour charges for laying premixed bituminous macadam concrete etc. by hot mix laid process including heating the asphalt and aggregate by continuous hotmix plant, transporting the mix and spreading the same by paver finisher and consolidation with power roller including providing and laying uniformly tack coat including necessary fire woods, oil, lubricants labour charges and hire charges of the required plant and machineries etc. complete.	398.00	MT	Rd & Bridge 15-16	26036	19
3	Providing and spreading tack coat using Bitumen VG10/30 on road surface before laying hotmix material including heating the bitumen and labour charges for applying bitumen on road surface at the rate 2.5 kg/ 10 smt. with carting on site etc. comp as directed by engg. in charge. (Never Use Tyre / Platic Material for heating the Bitumin)	140.00	MT	ARC Rate		
4	Re-carting of Hotmix material from place of Work / AMC store to Location of laying havind narrow width like chawls, poles, gamtal roads using JCB for loading to transorting by tractor trolley including fuel, driver etc complete as directed.	90.00	MT	ARC Rate		